

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-00584

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Knoll "A" No. 1

SEC. 4 T. 9 R. 25W
NW NW SW

Total Depth. 4080'
Comm. 11-8-57 Comp. 12-2-57
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 3-8-58

County Graham
KANSAS



Elevation. 2555' RB

Production. 27 BOPD plus 10% wtr.

Figures indicate Bottom of Formations.

sand, shale, shells	221
shale, shells	2235
Anhydrite	2291
shale, shells	2695
shale, lime	3745
lime	4080
Total Depth	

TOPS:	Sample Elec.
Anhydrite	2235 2234
Heebner	3790 3790
Toronto	3810 3812
Lansing	3826 3824
B/Kansas City	4080 4059

DST #1 3848-63 Open 1 hr., rec.
15' mud. BHP #0.

DST #2 3860-85 Open 2 hrs., rec.
90' HOOM, 20' froggy oil, 10' free
oil. BHP 980#.

DST #3 3901-12 Open 2 hrs., rec.
420' gas, 64' HOOM, 60' MCO. BHP
1066#.

DST #4 3946-73 Open 1 hr., rec.
20' mud w/specks of oil. BHP 50#.

DST #5 3973-95 Open 1 hr., rec.
20' mud. BHP 0#.

DST #6 3994-4020 Open 1 hr., rec.
25' mud. BHP 130#.

DST #7 4013-35 Open 1 hr., rec.
20' mud. BHP 30#.