

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-005-03121

Company- IMPERIAL OIL OF KANSAS, INC.  
 Farm- Victory Life No. 1  
 Ins. Co.

SEC. 6 T. 9 R. 25W  
 NE NE NE

Total Depth. 4080'  
 Comm. 12-18-58 Comp. 1-1-59  
 Shot or Treated.  
 Contractor.  
 Issued. 8-1-59

County Graham  
 KANSAS



Elevation. 2572' RB

Production. 312 BOPD - NW

CASING:

8 5/8" 228' cem w/150 sx.  
 5 1/2" 4080' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface sand & shale 228  
 shale & shells 1210  
 shale, shells, sand 1750  
 shale & shells 2278  
 Anhydrite 2316  
 shale & shells 2735  
 shale & lime 3860  
 lime 4080 RTD  
 Total Depth

TOPS:	SAMPLE	ELECTRIC
Anhydrite	2278	
Heebner	3819	3822
Toronto	3840	3843
Lansing	3858	3862

DST #1 3924-36', op 1 hr. rec. 1750' gas,  
 35' oil cut mud, 340' oil, 50' salt water.  
 BHP 1170#.

DST #2 3962-75', op 1 hr., rec. 20' mud  
 w/specks of oil. BHP 30#.

DST #3 3971-97', op 1 hr., rec. 2230'  
 salt water. BHP 1240#.

DST #4 4011-37', op 1 hr., gas to surface  
 in 1 hr., rec. 1240' free oil. BHP 1030#.