

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
808 EAST MURDOCK - WICHITA, KANSAS

15-065-20011

COMPANY **THEODORE GORE**

SEC. 8 T. 9 N. 25W
 LOC. C NE SE

FARM **Williams**

NO. 1

TOTAL DEPTH **4065**

COMM. **2-8-67**

COMP. **2-15-67**


SHOT OR TREATED

CONTRACTOR **Empire Drlg.**

ISSUED **3-18-67**

COUNTY **Graham**

KANSAS



CASING

20	10
15	8 5/8" @ 115' w/80 SX
12	6
13	5

ELEVATION **2522' KB**

PRODUCTION **DRY/KC**

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	320	Surface-Shale
320	to	1275	Shale & Bentonite
1275	to	1680	Shale
1680	to	1780	Shale & Gypsum
1780	to	1985	Sand
1985	to	2210	Shale
2210	to	2244	Anhydrite
2244	to	2665	Shale
2665	to	3125	Shale & Lime
3125	to	4065	Lime
4065			Rotary Total Depth

SET: 115' of 8 5/8" with 80 sacks cement.

SAMPLE LOG TOPS:

Anhydrite	2210	+312
Base Anhydrite	2244	+278
Heebner	3776	-1254
Toronto	3798	-1276
Lansing	3820	-1298
Muncie Creek	3938	-1416
Base Kansas City	4051	-1529
Total Depth	4065	-1543

CERTIFICATION

I, Theodore Gore, do hereby certify that the above and foregoing is a true and correct copy of the log on the Williams #1, NE NE SE Section 8-9S-25W, Graham County, Kansas, as reflected by the files of Empire Drilling Company.

Theodore Gore
 Theodore Gore

and sworn to before me, a Notary Public, within and for Sedgwick County,
 on 22nd day of February, 1967.