

KANSAS GEOLOGICAL SURVEY  
508 East Murdock  
Wichita, Kansas  
AUG 28 1971

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

17-9-25W  
CNE

15-005-20-180

ELEVATION: 2616'RB


WELL NO. 15-005-20-180  
KNOBEL #2

C NE Sec. 17-9S-25W

Graham County, Kansas

DRY/LKC

KANSAS



Commenced: August 12, 1971

Completed: August 19, 1971

OPERATOR: Derrick-American Oil, Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	100	Clay - Sand	Ran 5 joints of New 20# 8 5/8"
100	2296	Shale & sand	Csg set @ 212' w/175 sks Common
2296	2330	Anhydrite	w/2% Gal & 3% CC.
2330	2640	Shale	P.D. @ 6:45 PM 8/12/71
2640	3465	Shale & Lime	Cement Circ. Job by Globe
3465	3900	Lime & Shale	Centralizer @ 197'
3900	3975	Lime	
3975	4025	Lime & Shale	
4025	4104	Lime	
4104	4112	Lime & Shale	
4112	TD		Dry & Abandoned

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE Sec. 17-9S-25W, Graham County, Kansas, to the best of my knowledge and belief.

  
James S. Sutton II

SAMPLE TOPS:

DST (1) 3875-3975  
DST (2) 4001-4112

Heebner 3875  
Toronto 3901  
LKC 3919