

KANSAS

WELL COMPLETION REPORT AND *State Geological Survey*
DRILLER'S LOG

WICHITA BRANCH


API No. 15 _____ County _____ Number _____

S. 20 T. 9S R. 25 ^{EX} W

Loc. SW NE NE

County Graham

640 Acres
N



Locate well correctly

Elev.: Gr. 2609

DF 2612 KB 2614

Operator
J. A. Allison

Address
300 W. Douglas, Suite 305 Wichita, KS 67202

Well No. 2 Lease Name Rome

Footage Location
990 feet from (N) (S) line 990 feet from (E) (W) line

Principal Contractor Big Springs Drilling Geologist Orlin R. Phelps

Spud Date 10/13/80 Date Completed 10/23/80 Total Depth 4131 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"		233'	Common	190	2%CC, 3%Gel
Casing		4-1/2"		2285'	50/50 Pozmix	500	6% Jel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls. Gas _____ MCF Water _____ bbls. Gas-oil ratio _____ CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator J. A. Allison		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole
Well No. 2	Lease Name Rome	Will complete as SWD
S 20 T 9 R 25 ^{XX} W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST#1, op 30 si 30; op 30, si 30; rec. 10' mud, fair show, spotted free oil, ISIP 54, FSIP 54; IFP 32, FFP 32.	3857	3895	<u>ELECTRIC LOG TOPS</u>	
DST#2, op 30, si 30; op 30, si 30; rec. 15' mud, specks oil, ISIP 1197, FSIP 1176; IFP 32-32, FFP 43-43, Temp. 118°.	3917	3939	Anhydrite	2277 (+ 337)
DST#3, op 30, si 30; op 30, si 30; rec. 5' mud, ISIP 32, FSIP 32, IFP 11-11, FFP 11-11, Temp. 111°.	3938	3952	Heebner	3859 (-1245)
DST#4, op 30, si 45; op 60, si 45; rec. 180' watery mud, sl show oil, ISIP 1251, FSIP 1219; IFP 32-43, FFP 65-97, Temp. 115°, chl. 65,000 good show and odor.	3962	3990	Toronto	3884 (+1270)
DST#5, op 30, si 30; op 30, si 30; rec. 62' sl. oil cut mud, 2% oil, 98% mud, ISIP 1133, FSIP 553; IFP 43-54, FFP 54-54, Temp. 109°.	4014	4065	Lansing	3904 (-1290)
DST#6, op 30, si 30; op 30 si 30; rec. 20' sl. oil cut mud, 10% oil, 120' gas in pipe, ISIP 82#, FSIP 108; IFP 22-22, FFP 26-26.	4063	4086	BKC	4126 (-1512)
			RTD	4131 (-1517)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	J. A. Allison Operator
	Title
	November 4, 1980 Date

80089

20-9-25W

71

BIG SPRINGS DRILLING, INC.

P.O. BOX 8287
MUNGER STATION
WICHITA, KANSAS 67208

State Geological Survey
WICHITA BRANCH

SUITE 29 • 400 NORTH WOODLAWN • (316) 681-1732

October 28, 1980

RE: Rome #2
SW NE NE
Sec. 20 Twp 9S RG 25W
Graham County, Kansas

OPERATOR: J. A. Allison
CONTRACTOR: Big Springs Drilling, Inc.
COMMENCED: October 13, 1980
COMPLETED: October 22, 1980

Surface Pipe: Set 233' of 8 5/8" w/190 SX Common 2% gel 3% cc1

0	233	Clay, Shale & Sand
233	2278	Shale & Sand
2278	2312	Anhydrite
2312	3080	Shale
3080	3895	Shale & Lime
3895	4130	Lime
4130		RTD

We certify that the above and foregoing is a true and correct copy of the log on the Rome #2 located in Graham County, Kansas.

Big Springs Drilling, Inc.

Paul A. Seymour, Jr.
Paul A. Seymour, Jr.

Subscribed and sworn to before me this 28th day of October, 1980.



Ruth M. Bassett
Ruth M. Bassett

My Commission Expires:

May 30, 1983

