

15-065-20018

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **BANKOFF & LEBEN**

SEC. 28 T. 9 R. 25W
LOC. SE SE SW

FARM **Bollig**

NO. 5

COUNTY **Graham**

TOTAL DEPTH **4035**


COMM. **3-7-67**

COMP. **3-16-67**

SHOT OR TREATED

CONTRACTOR **Leben Drlg.**

ISSUED **7-1-67**



CASING

20	10
15	8 5/8" @ 248' w/150 sx
12	6
13	5

ELEVATION **2560' KB**

PRODUCTION **PMP 25 BOPD, NW**
LKC 3850-62; 3869-73;
3963-67

FIGURES INDICATE BOTTOM OF FORMATIONS

0	40	Clay, Post Rock
40	248	Sand, Shale
248	1725	Shale
1725	2125	Shale, Sand, Redbed
2125	2183	Shale, Shells
2183	2221	Anhydrite
2221	3214	Shale, Lime
3214	3351	Lime
3351	3818	Lime, Shale
3818	4035	Lime
	<u>4035</u>	<u>RTD - Set 5 1/2" Casing</u>

8 5/8" 8 rd. 20# new surface casing set @ 248' cemented with 150 sacks Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Bollig #5 Well, located SE SE SW of Section 28, Township 9 South, Range 25 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite

TOPS: SCOUT

Heebner
Toronto
Lansing

3788
3811
3825