

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-00652

Company- IMPERIAL OIL CO.

Farm- Richmeier

No. 1

SEC. 30 T. 9 R. 25W
C NE SE

Total Depth. 4400'

Comm. 6-8-61

Comp. 6-20-61


Shot or Treated.

Contractor. Imperial Oil of Kans.

Issued. 9-16-61

County Graham

KANSAS



CASING:

8 5/8" 189' cem w/150 sx.

4 1/2" 4083' cem w/100 sx.

Elevation. 2604' RB

Production. 124 BOPD

Figures indicate Bottom of Formations.

surface clay & sand	189
shale & sand	1790
Dakota sand	2000
shale & red bed	2040
shale & shells	2240
Anhydrite	2274
shale & shells	2320
shale & lime	2700
shale & shells	2895
shale & lime	3712
lime	4400 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Anhydrite (scout)	2240	
Heebner	3844	3843
Toronto	3862	3863
Lansing	3876	3876
Base Kansas City	4110	4107
Marmaton	4136	4136
Cherokee Shale	4330	4328
Cherokee Lime	4340	4340

DST #1 3873-90', op 1/2 hr, rec. 5' mud,
ICIP 810#, IFP 0#, FFP 0#, FBHP 760#/20 mins.

DST #2 4028-54', op 1½ hrs, rec. 560' gas,
60' slightly oil cut mud, 60' oil cut mud,
120' heavily oil cut mud, 60' muddy oil.
ICIP 1260#, IFP 0#, FFP 60#, FBHP 1090#/20 mins.

DST #3 4053-72', Packer failure.

DST #4 4050-72', op 1 hr, rec. 50' mud,
ICIP 1190#/ IFP 0#, FFP 0#, FBHP 1000#.