

30-9-25W
NE SW NW

SEP 25 1971

CONTRACTOR'S WELL LOG

Elevation: 2627'KB

DRY/BKC

15-005-20489

OPERATOR:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	<u>WERTH #1</u>
LOCATION:	<u>NE SW NW, Sec. 30-9S-25W</u> Graham County, Kansas
GEOLOGIST:	Jack K. Wharton
SPUD DATE:	September 18, 1971
COMPLETION DATE:	September 26, 1971

0	50	Clay
50	80	Sand
80	180	Clay & Shale
180	237	Shale
237	1220	Shale & Shells
1220	1300	Shale
1300	1380	Sand
1380	1730	Shale
1730	1866	Shale & Sand Streaks
1866	2044	Sand
2044	2268	Shale (Red Red)
2268	2308	Anhydrite
2308	2970	Shale & Lime
2970	3145	Lime & Shale
3145	4155	Lime
	4155	Rotary Total Depth

Drilled 237' of 12½" surface hole, set 8-5/8" csg. at 235' K.B. w/150 sx. cement. Cement circulated. Plug was down at 4:45 p.m. 9-18-71.
Dry and Abandoned

ELECTRIC LOG TOPS

ELEVATION

Anhydrite	2276 (+ 351)	2627 K.B.
B/Anhydrite	2310 (+ 317)	2625 D.F.
Heebner	3865 (-1238)	2519 G.L.
Toronto	3887 (-1260)	
Lansing	3900 (-1273)	
Base/K.C.	4134 (-1507)	
ELTD	4158 (-1531)	

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WERTH #1, NE SW NW, Sec. 30-9S-25W, Graham County, Kansas.