

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-065-00676

Company HEATHMAN-SEELIGSON DRILLING CO.
 Farm- Brungardt "A" No. 1

SEC. 32 T. 9 R. 25W
 SW SW NE

Total Depth. 4425

Comm. 11-9-55

Comp. 11-20-55


Shot or Treated.

Contractor. Heathman-Seeligson Drilling Co.

Issued. 12-31-55

County Graham

KANSAS



CASING:

8 5/8 @ 200.75' w/ 125 sx cmt.

Elevation. 2585 DF

Production. Dry

Figures indicate Bottom of Formations

clay & shale	140
sand	180
shale & shells	200
shale & sand	1310
sand	1375
shale & sand	1485
shale & shells	1805
sand	2000
shale & red bed	2040
shale & shells	2227
anhydrite	2276
shale; shells & red bed	2370
shale, shells & lime	2712
lime & shale	3850
lime	4063
lime & shale	4335
shale	4378
lime & shale	4410
lime, shale & chert	4425
Total Depth	

TOPS: (KB)

Anhydrite	2227
Heebner	3826
Toronto	3850
Lansing	3764
Base K. C.	4096
Marmaton	4144
Marmaton cherty lime	4195
Marmaton cherty conglomerate	4410
Mississippian chert	4422

DST #1: 3537-85, open 45 min. 2 min.
 blow, rec. 3' mud, BHP 100#

DST #2: 4020-40, open 1 hr. 15 min.
 rec. 20' mud, BHP 580#

DST #3: 4045-63, Mis-run

DST #4: 4044-63, open 2 hrs. rec. 65'
 muddy SW, BHP 180#