


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 500 East Murdock, Wichita, Kansas

Company: THE TEXAS COMPANY
 Farm: Joseph Kuhn "B" No. 1

SEC. 33 T. 9 R. 25W
 APPROX. C NE SE
 100' SE of C NE SE

Total Depth: 4250'
 Comm: 11-30-58 Comp: 12-11-58
 Shot or Treated:
 Contractor: Stickle Drlg.
 Issued: 4-4-59

County Graham
 KANSAS



Elevation. 2516' DF

Production. 168 BOPD

CASING

8 5/8" 329' cem w/240 sx.
 5 1/2" 4237' cem w/125 sx.

Figures indicate Bottom of Formations.

surface	0
sand & shale	120
shale & shells	1225
sand	1445
shale & sand	1550
shale & shells	1710
sand	1925
sand & shale	2000
shale & shells	2162
Anhydrite	2203
shale & Shells	2600
shale & lime	2870
shale & lime strks	3020
shale & lime	3135
lime & shale	3794
lime	4047
shale & lime	4097
lime & shale	4167
shale & lime	4250
Total Depth	

TOPS: SCOUT	
Topeka	3554
Heebner	3768
Toronto	3791
Lansing	3809
Base Kansas City	4038
Cherokee	4236

Ran Gamma Ray - Neutron & Lateral Log
 Correlation Log.

Perfs: 4012-16', 3988-90', 3965-79', 3945-50'.