

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-01639

Company- THE TEXAS COMPANY
Farm- Joseph Kuhn No. 2

SEC. 34 T. 9 R. 25W
C NE SE
660' S & 660' W. of NE Cor. SE/4

Total Depth. 4051'
Comm. 12-27-58 Comp. 1-5-59
Shot or Treated.
Contractor. Stickle Drilg. Co.
Issued. 5-30-59

County Graham
KANSAS



Elevation. 2554' DF

Production. 135 BOPD

CASING:

8 5/8" @ 322' cen. w/240 sx.
5 1/2" @ 4042' cen. w/160 sx.

Figures Indicate Bottom of Formations.

Measurements: BH to KB 3' - BH to GL 3'

surface	0
shale	40
shale sand & shells	810
shale	1210
Dakota sand	1410
shale & shells	1430
sand & shale	1560
shale & shells	1770
sand & shells	2188
Anhydrite	2230
shale	2240
shale & shells	2640
shale & lime	2830
shale & lime strks.	2975
shale & lime	3355
lime & shale	3585
lime	3705
shale & lime	3808
lime & shale	3855
lime	4050
lime	4051
Total Depth	

TOPS: SCOUT

Topeka	3580
Heebner	3799
Toronto	3821
Lansing	3837

Logs Run: Schlumberger Gamma Ray - Laterlog & Sonic.

Centralizers: 4006-3911-3815-2240-281

Completion Data: Formation - Lansing
Depth of Prod. Interval: Perfs.
3867-70, 3879-84, 3976-81, 4001-04,
4018-24 & OH 4042-51.