

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

15-065-20074

SEC. 35 T. 9 R. 25W
 LOC. 150' W of C NE NW


COMPANY **BANKOFF & LEVEN**

FARM **Spies** NO. **1**

TOTAL DEPTH **4085'**
 COMM. **8-10-67** COMP. **8-18-67**
 SHOT OR TREATED
 CONTRACTOR **Leben Drlg.**
 ISSUED **9-23-67**

COUNTY

Graham
KANSAS



CASING

| | | |
|----|----|-------------------------|
| 20 | 10 | |
| 15 | 8 | 5/8" 251' cem w/ 175 sx |
| 12 | 6 | |
| 13 | 5 | |

ELEVATION **2561' KB**

PRODUCTION **DRY(B KC)**

| | | | |
|------|-------------|--------------------------|--------------------|
| 0 | 150 | Clay, Sand | |
| 150 | 251 | Shale, Shells | |
| 251 | 1280 | Shale | |
| 1280 | 1515 | Sand, Shale | |
| 1515 | 1940 | Sand, Redbed | |
| 1940 | 2060 | Shale, Shells | |
| 2060 | 2200 | Shale | |
| 2200 | 2230 | Anhydrite | TOPS: SMP |
| 2230 | 2380 | Shale | Anhydrite 2200 |
| 2380 | 2830 | Shale, Lime | B Anhydrite 2230 |
| 2830 | 2960 | Lime, Shale | Heebner 3815 |
| 2960 | 3155 | Shale, Lime | Toronto 3838 |
| 3155 | 3640 | Lime, Shale | L Kansas City 3849 |
| 3640 | 3765 | Topeka Lime | B Kansas City 4082 |
| 3765 | 3956 | Lime | |
| 3956 | 4042 | Kansas City Lime | |
| 4042 | 4085 | Lime | |
| | <u>4085</u> | <u>RTD - D. & A.</u> | |

8 5/8" new 17.65# surface casing set @ 251' cemented with 175 sacks
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Spies #1 Well, located 150' West of C NE NW of Section 35, Township 9 South, Range 25 West Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
)
 COUNTY OF BARTON) SS