

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-17A-05605

Company- M.J. BOVE
Farm- Transue

No. 2

SEC. 18 T. 9
SE NW SE

R. 26W

Total Depth. 4042'

Comm. 9-24-63

Comp. 10-6-63


Shot or Treated.

Contractor. Emprie Drilling Co.

Issued. 1-25-64

County Sheridan

KANSAS



Elevation. 2682' KB

Production. 40 BOPD, NW

CASING:

8 5/8" 311' cem w/140 sx.

4 1/2" 4041' cem w/50 sx. & 600 Gal. Latex

Figures Indicate Bottom of Formations.

surface hole	316
shale & clay	500
shale & shells	1800
sand-shale-redbed	2260
shale	2268
Anhydrite	2301
shale	2340
shale-shells	2650
lime & shale	2724
shale & Shells	2850
lime & shale	2940
lime	3000
lime & shale	3185
lime	3235
lime & shale	3310
lime	3370
lime & shale	3650
lime	3710
shale & lime	3810
lime	4042 RTD
Total Depth	

TOPS: ELECTRIC LOG

Anhydrite	2267
Topeka	3596
Heebner	3775
Toronto	3799
Lansing	3816
Zone 2	3843
Zone 2A	3857
Zone 6	3947
Zone 6A	3972
Zone 7	3990
Zone 8	4010
Zone 9	4032