

KANSAS DRILLERS LOG

S. 18 T. 9 R. 26 E W

Loc. C NE SE

County Sheridan

API No. 15 — 179 — 20,457
County Number

Operator

The Maurice L. Brown Company and I. Wayne Woolsey and KRM

Address

1500 Vickers KSB&T Building Wichita, Kansas 67202

Well No.

#2

Lease Name

Transue

Footage Location

1980 feet from (N) (S) line

660 feet from (E) (W) line

Principal Contractor

Abercrombie Drlg. Inc.

Geologist

Ralph H. White

Spud Date

4/23/77

Total Depth


4100'

P.B.T.D.

Date Completed

Oil Purchaser

640 Acres
N



Locate well correctly

Elev.: Gr. 2685

DF KB 2693'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	23	254	Common	200	3% Ca. Cl.
Production	7 7/8"	5 1/2"	14-15 1/2	1792	Pozmix 50/50	150	2% gel, 10% Sodium Chl.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator The Maurice L. Brown Company, I. Wayne Woolsey & KRM		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 2	Lease Name Transue	SWDW
S 18 T 9S R 26 EX W Sheridan County		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Well taken over by KRM. To be completed as salt water disposal well.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Geologist Title May 18, 1977 Date
---------------	---

92689

CONTRACTOR'S WELL LOG

OPERATOR: The Maurice L. Brown Co.
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: TRANSUE #2
LOCATION: C NE SE, Section 18-9S-26W
Sheridan County, Kansas
SPUD DATE: 4-23-77
COMPLETION DATE: 5-04-77

0	255	Clay, Sand & Shale
255	1300	Shale
1300	2075	Sand & Shale
2075	2278	Shale
2278	2316	Anhydrite
2316	2870	Shale
2870	3197	Shale & Lime
3197	3556	Lime & Shale
3556	3638	Lime
3638	3806	Lime & Shale
3806	3838	Lime
3838	3883	Lime & Shale
3883	3886	Lime
3886	3972	Shale & Lime
3972	4010	Lime
4010	4077	Shale & Lime
4077	4100	Lime
	4100	Rotary Total Depth

Spud hole at 1:00 p.m. 4-23-77. Drilled 255' of 12 $\frac{1}{4}$ " hole. Ran 6 jts. of new 23# - 8 5/8" Surface Casing. (Tally 245.81') Set at 254.31'. Cemented with 200 sx. of common cement, 3% Ca. Cl. Cemented did circulate. Plug was down at 6:00 p.m. 4-23-77.

T.D. 4100', Ran 1792' of 5 $\frac{1}{2}$ " Casing. Cemented with 120 sx. 50/50 posmix, 2% gel. Job was complete at 2:45 p.m. 5-04-77.

SAMPLE TOPS:

Anhydrite 2278' (+415)
B/Anhydrite 2316' (+377)

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the TRANSUE #2 C NE SE, Section 18-9S-26W, Sheridan County, Kansas.

The Maurice L. Brown Company,
I. Wayne Woolsey & KRM Petroleum Corp.

#2 Transue

C NE SE
Sec. 18-T9S-R26W

Contr. Abercrombie Drilling Co.

Sheridan County

Elev. 2693' KB

Comm. 4/24/77

Comp. 5/4/77

IP SWDW

Casing: 8 5/8" 254'/200 sx
5 1/2" 1792'/150 sx

<u>Log Top</u>	<u>Depth</u>	<u>Datum</u>
Stone Corral	2282	+ 411
Howard	3527	- 834
Topeka	3587	- 894
Heebner	3797	-1104
Toronto	3824	-1131
Lansing	3838	-1145
BKC	4067	-1374
Total Depth	4100	-1407

DST #1 3826-3838'
45"-45"-45"-60"
Rec. 11' M
IFP 20-20#
ISIP 41#
FFP 20-20#
FSIP 61#

DST #4 3997-4010'
45"-45"-45"-60"
Rec. 20' M
IFP 10-10#
ISIP 20#
FFP 10-10#
FSIP 20#

DST #2 3868-3883'
45"-60"-45"-90"
Rec. 124' M w/oil spks., 124' GCM w/oil spks.,
62' G&WCM w/oil spks. & 124' GCMW
IFP 41-183#
ISIP 895#
FFP 183-244#
FSIP 885#

DST #5 4012-4037'
Misrun-Packer failure
DST #6 4008-4037'
Misrun-Packer failure

DST #3 3945-3972'
45"-45"-45"-60"
Rec. 77' M w/sli. tr. oil
IFP 41-51#
ISIP 1274#
FFP 51-61#
FSIP 1264#

DST #7 3997-4037'
45"-60"-45"-90"
Rec. 22' M
IFP 41-51#
ISIP 71#
FFP 41-51#
FSIP 61#

Well taken over by KRM. To be completed
as salt water disposal well.