



KANSAS GEOLOGICAL SURVEY
508 East Wardock
Wichita, Kansas

Shields

19-95-26W
Russell, Kansas


JUL 19 1969

WELL LOG

Operator: Shields Oil Producers, Inc.
Well: Minium #1
Commenced: June 7, 1969
Completed: June 14, 1969
Contractor: Shields Drilling Co., Inc.

Well Description

W/2 NE/4
Sec. 19-9S-26W
Sheridan Co., Kansas



Size	Run	Pulled
8 5/8"	305'	Cmtd. w/ 200 sax

Elevation: 2,672' RB

Treatment:

Production: D & A

Tops:	Heebner	3,776'
	Toronto	3,799'
	Lansing-KC	3,816'

..... Figures Indicate Bottom of Formations

Shale, sand & shale	312'
Shale & sand	1,405'
Shale, sand & shells	1,800'
Shale, shells & redbed	2,245'
Anhydrite	2,295'
Shale & shells	2,630'
Shale & lime	3,240'
Lime	3,330'
Lime & shale	3,505'
Lime	3,640'
Lime & shale	3,695'
Lime	4,016' RTD

NOTES

DST #1 3,825' - 3,870'

Tool open 1 hr. w/ weak blow for 20 min.
Recovered 30' mud. IBHP-1,241#,
IFP-51#, FFP-72#, FBHP-not taken.

DST #2 3,865' - 3,900'

Tool open 1 hr. w/ good blow thruout.
Recovered 960' muddy salt water. IBHP-1,352#,
IFP-68#, FFP-502#, FBHP-1,335#/30 min.

DST #3 3,930' - 4,016'

Tool open 1 hr. w/ weak blow for 20 min.
Recovered 40' mud. IBHP-1,105#, IFP-68#,
FFP-111#, FBHP-918#/30 min.