

Stephen C. Robben

Box 426

Phone 913-735-9405

Victoria, Kansas 67671

32-9-26W

Skyline Petroleum
Minium # 1
SE/NE/NW
32/9/26W
Sheridan Co., Kansas

CONFIDENTIAL

Completion Report

11/25/85 Moved in Express Well Service double drum. Ran Correlation log and Cement Bond log. P.B.T.D. 4075'. Swabbed hole dry. Perforated from 4048-50', (K-zone). No fluid natural. Treated zone with 750 gallons of acid (15% N.E.). Maximum pressure 1000#. Treated at 2 BPM 400#. ISIP 250# 5 minutes. Bled back 9 BBL. 117 BBL load. Swabbed down to 2000'.

11/26/85 2000' down to fluid.

Swab down - 101.0 BBL

30 min. - 2.3 BBL Scum of oil

Perforated from 4012-14' (I-zone). Set Retreivable plug at 4035'. Swabbed 1.6 BBL in 30 minutes (100% oil). Treated zone with 1250 gallons of acid (28% N.E.). Maximum pressure 500#. Treated at 3 BPM 375#. ISIP 300#. 200# in 5 minutes. 15 minutes 100#. Shut in 1 hour. 153 BBL load.

Swab down - 133.0 BBL

4 pulls 1 hr. - 18.5 BBL 200' off bottom 75-80% oil

11/27/85 1100' of fluid in hole, trace of water.

Swab down - 39.0 BBL

2 pulls 30 min. - 6.8 BBL 80% oil

Perforated from 3876-78' (B-zone). Set Retreivable plug at 3920'. Swabbed 2 BBL in 30 minutes, 100% oil. Treated zone with 1250 gallons of acid (28% N.E.). Maximum pressure 600#. Treated at 3 BPM 250#. ISIP 250#. 30 minutes 75#. 149 BBL load.

Swab down - 126.0 BBL

4 pulls 1 hr. - 18.5 BBL 55-60% oil 150' off bottom

1 pull 30 min. - 4.6 BBL 65% oil 150' off bottom

STATE OF KANSAS

JAN 24 1986

CONFIDENTIAL DIVISION

32-9-26w

Stephen C. Robben

Box 426

Victoria, Kansas 67671

Phone 913-735-9405

Skyline Petroleum
Minium # 1

11/29/85 3000' of fluid in hole (900' water & 2100' oil). Opened Port collar at 2282' and circulated cement with 450 sacks of 50-50 poz-mix, 6% gel.

Pulled plug.

12/2/85 Ran tubing and rods.

CONFIDENTIAL

January 1, 1986
Geological Survey
VICTORIA BRANCH