

KANSAS DRILLERS LOG

State Geological Survey
WICHITA BRANCH

API No. 15 — 179 — 2043
 County Number

S. 9 T. 9S R. 27 ^{NE} _W
 Loc. N/2 N/2 SE/4
 County Sheridan

Operator
Rains & Williamson Oil Co., Inc.

Address
435 Page Court, 220 W. Douglas, Wichita, Kansas 67202


Well No. #1 Lease Name McFadden 'B'

Footage Location
 feet from (N) (S) line _____ feet from (E) (W) line _____

Principal Contractor Rains & Williamson Oil Co., Inc. Geologist Tom Wesselowski

Spud Date 8-22-76 Total Depth 4110' P.B.T.D. _____

Date Completed 8-31-76 Oil Purchaser _____



Elev.: Gr. _____
 DF _____ KB 2726

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4"	8 5/8"	20#	326'		200 sx.	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbis.	MCF	bbis.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rains & Williamson Oil Co., Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole

Well No. #1 Lease Name McFadden 'B'

S 9 T 9S R 27 W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 3825-3880, 30 (30) 30 (30). Rec. 10' mud. FP's 26, 34. IBHP 582, FBHP 462.			E. Log Tops	
DST #2 - 3882-3905, 30 (30) 60 (30). Rec. 15' oil, 60' OCM, 120' muddy water. FP's 13, 92. IBHP 1188, FBHP 1175.			Anhydrite	2315 (+411)
			B/Anhydrite	2350 (+376)
			Heebner	3828 (-1102)
			Toronto	3854 (-1128)
			Lansing	3871 (-1145)
			BKC	4095 (-1369)
			LTD	4114 (-1388)
DST #3 - 3978-4005, 30 (30) 90 (45). Rec. 10' oil, 60' HOcm, 90' gas in pipe. FP's 13, 52. IBHP 793, FBHP 767.				
DST #4 - 4008-4048, 30 (30) 30 (30). Rec. 5' mud. FP's 26, 26. IBHP 87, FBHP 87.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____



 Wilson Rains Signature

 President Title

 12-14-78 Date

H-269