

OCT 11 1969

WELL LOG

Chief Drilling Co., Inc.
905 Century Plaza
Wichita, Kansas 67202

#1 VICKERS
Approx. SW SW SW
Sec. 31-9-27W
Sheridan County

Contractor: Chief Drilling Co., Inc.

Casing Record: Set 197' of 8 5/8" @ 206'
w/175 sacks Common Quickset.

Commenced: 8-17-69
Completed: 8-23-69

Dry

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & clay	0	1165	2714 Gr.
Shale, shells & sand strks.	1165	1286	2716 D.F.
Shale & sand	1286	1660	2719 K.B.
Shale, shells & sand strks.	1660	1930	
Sand	1930	2075	
Red bed & shale	2075	2245	
Red bed, shale & sand	2245	2290	
Anhydrite	2290	2325	
Shale & shells	2325	2414	
Shale & lime	2414	2760	
Shale & lime	2760	4050	
Lime	4050	4120	
T.D.	4120		

<u>FORMATION TOPS</u>	
Anhydrite	2290 + 429
Heebner	3826 -1107
Toronto	3848 -1129
Lansing	3864 -1145
T.D.	4120 -1401

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the approximate SW SW SW of Section 31-9-27W, Sheridan County, Kansas, to the best of my knowledge and belief.

Chief Drilling Co., Inc.

Jim Robinson
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 26th day of August, 1969.

Betty Brandt
Betty Brandt, Notary Public

My Commission Expires:
May 9, 1971