

FORMATION TESTING SERVICE

P.O.Box 518, Hays, Kansas 67601
Telephone (913) 628-1115

Test# 1 10-9-27W
Zone Tested: Lansing "B"
Lease Name: White #1
Location: Sec. 10 Twp. 9S Rng. 27W
County Sheridan St. Kansas

Company: Sharon Resources
Company Address: Engelwood, Colorado
Company Representative: Mr. Robert Elder
Contractor: Murfin Rig #2

Date: 11/16/84
Elevation: 2706 KB
Tester: Mr. John L. Schmeidler

Interval Tested: 3873'-3920'
Internal Recorder-Type: AK-1 Range: 4200' No: 7432 Depth: 3920'
External Recorder-Type: AK-1 Range: 4000' No: 13754 Depth: 3900'

Initial Hydrostatic Mud: 1886 P.S.I.

Initial Flow Pressure 39 To 108 P.S.I.

Initial Flow Period 30 Min.

Initial Shut-In Pressure 1056 P.S.I.

Initial Shut-In 45 Min.

Final Flow Pressure 118 To 157 P.S.I.

Final Flow Period 45 Min.

Final Shut-In Pressure 1046 P.S.I.

Final Shut-In 60 Min.

Final Hydrostatic Mud 1881 P.S.I.

Temperature: 116° Tool Open: 12:55 am

Blow: Steadily increasing to 8" blow both

Mud Weight 9.6 Viscosity 49 Water Loss 8.0

8 strokes - 5 sec return second shut-in.

Total Depth: 3920'

RECEIVED

Anchor Length: 47'

APR 29 1985

Bottom Packer: 3973'

CONSERVATION DIVISION

Top Packer: 3968'

Wichita, Kansas

Surface Choke: 1"

Bottom Choke: 3/4"

Drill Pipe Size: 4 1/2" FH

Collars Run: 210' I.D. 2.25

Wt. Pipe Run: 660' I.D. 2.75

Main Hole Size: 7 7/8"

Rubber Size: 6 5/8"

410' Feet Total Recovery

Recovered 150' Feet clean slightly gassy oil 31 ⁸⁰ A.P.I.

Recovered 150' Feet heavy mud cut oil--65% oil, 35% mud

Recovered 110' Feet heavy mud cut oil, 45% oil, 10% water, 45% mud

Recovered Feet

Extra Equipment: Jars, safety joint, sampler


Price of Job: \$1100.00

650.00 DST

450.00 Extra Equipment

Pi

10-9-27w
1 white



MAY 02 1985

POINT

(A) Initial Hydrostatic Mud	1886	PSI
(B) First Initial Flow Pressure	39	PSI
(C) First Final Flow Pressure	108	PSI
(D) Initial Closed-in Pressure	108	PSI
(E) Second Initial Flow Pressure	118	PSI
(F) Second Final Flow Pressure	157	PSI
(G) Final Closed-in Pressure	1046	PSI
(H) Final Hydrostatic Mud	1881	PSI

State Geological Survey
BRANCH

RECEIVED
STATE CONSERVATION COMMISSION

APR 20 1985

CONSERVATION DIVISION
Wichita, Kansas

FILE NO. DATE

FORMATION TESTING SERVICE

P.O.Box 518, Hays, Kansas 67601
Telephone (913) 628-1115

10-9-27
P. Und

Test# 2
Zone Tested: Kansas City "G"
Lease Name: White #1
Location: Sec. 10 Twp. 9S Rng. 27W
County Sheridan St. Kansas
Date: 11/16/84
Elevation: 2706 K.B.
Tester: Mr. John L. Schmeidler

Company: Sharon Resources
Company Address: Engelwood, Colorado
Company Representative: Mr. Robert E. Elder

Contractor: Murfin Rig #2 Interval Tested: 3916'-3952'

Internal Recorder-Type: AK-1 Range: 4200' No: 7432 Depth: 3952'

External Recorder-Type: AK-1 Range: 4000' No: 13754 Depth: 3917'

Initial Hydrostatic Mud: P.S.I. 1930

Initial Flow Pressure 39 To 285 P.S.I. Initial Flow Period 30 Min.

Initial Shut-In Pressure 1176 P.S.I. Initial Shut-In 45 Min.

Final Flow Pressure 290 To 511 P.S.I. Final Flow Period 45 Min.

Final Shut-In Pressure 1176 P.S.I. Final Shut-In 60 Min.

Final Hydrostatic Mud 1915 P.S.I.

Temperature: 129° Tool Open: 3:23 p.m.

Mud Weight 9.1 Viscosity 44 Water Loss 9

Total Depth: 3952'

Anchor Length: 36'

Bottom Packer: 3916'

Top Packer: 3911'

Surface Choke: 1"

Bottom Choke: 1"

Drill Pipe Size: 4 1/2" FH

Collars Run: 210' I.D. 2.25

Main Hole Size: 7 7/8"

Blow: Steadily increasing to off-bottom
blow both openings.

Remarks No return on shut-ins.

Sampler: 2400 C.C. salt water

Wt. Pipe Run: 660' I.D. 2.75

Rubber Size: 6 5/8"

1120 Feet Total Recovery

Recovered 1120 Feet salt water, 41,600 p.p.m. Cl

Recovered Feet

Recovered Feet

Recovered Feet

Extra Equipment: Jars, safety joint, sampler Price of Job: \$1100.00

650.00 DST

450.00 Ext. Equipment

State Geological Survey
WICHITA BRANCH
1985


RECEIVED
STATE CORPORATION COMMISSION

APR 29 1985

CONSERVATION DIVISION
Wichita, Kansas

R.

10-9-27w
1 White



MAY 3 2 1935

RECEIVED
STATE CORPORATION COMMISSION

APR 29 1935

POINT

State Geological Survey
WICHITA, KANSAS

CONSERVATION DIVISION
Wichita, Kansas

(A) Initial Hydrostatic Mud	1930	PSI
(B) First Initial Flow Pressure	39	PSI
(C) First Final Flow Pressure	285	PSI
(D) Initial Closed-in Pressure	1176	PSI
(E) Second Initial Flow Pressure	290	PSI
(F) Second Final Flow Pressure	511	PSI
(G) Final Closed-in Pressure	1176	PSI
(H) Final Hydrostatic Mud	1915	PSI