


KANSAS GEOLOGICAL SOCIETY
508 East Murdock
Wichita, Kansas

MAR 1 1968

Distributed By
KANSAS GEOLOGICAL SOCIETY
508 East Murdock
WICHITA, KANSAS 67214
~~GILBERT L. HALL, INC.~~
~~WICHITA, KANSAS~~
~~DRILLERS' LOG~~

24-9-28W



15-179-20156

OCHS #1

NE NW NW Section 24-9S-28W
Sheridan County, Kansas

Commenced: November 2, 1968
Completed: November 10, 1968

Proved - oil

OPERATOR - Glen N. Rups

DEPTH		FORMATION	REMARKS
From	To		
0	185	Surface clay, shale and sand	
185	280	Shale	Ran 7 joints 8-3/8" casing, set @ 280' w/200 sacks cement.
280	1500	Shale	
1500	1735	Shale and shells	
1735	1835	Shale	
1835	2010	Shale and shells	
2010	2140	Sandy red bed	
2140	2378	Shale	
2378	2411	Anhydrite	
2411	2900	Shale	
2900	3750	Lime and shale	
3750	3890	Lime	
3890	3925	Lime and shale	
3925	4167	Lime	
4167	TD		Ran 103 joints 4-1/2" casing, set @ 4167' w/150 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the NE NW NW Section 24-9S-28W, Sheridan County, Kansas, to the best of my knowledge and belief.

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 14th day of November, 1968, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.