

LATON

Form 113 50M 8-49-48374-D

State Kansas County RooksSec. 3 Twp. 9 Rng. 16W Elev. 1991Company Vickers Pat.Well No. 5 Name GambleLocation NW NW SW

Feet from lines: N. S. E. W.

Spud 10-18-49 Completed 11-16-49T. D. 3316 Casing 5" 3316Comp. Perf. 56 § 3132-3202Pay 3132-3202 in Lans.I. P. 75 BOPD + 20% wtr.

Choke T. P. C. P.

G. O. R. Grvty.

DATE	REMARKS
11-16-49	Heeb. 3066, Tor. 3086, Lans. 3104 RTD 3316, DP GO 3305, 24 § 3287-95, 36 § 3255-68, FU 60' oil & mud, 2000 A, Swb/

DATE

REMARKS

1/4 BFPH, FU 1000' fluid/13 hr.

2/3 oil.

PB 3230, 2 1/4 @ 3190-3202

FU 850' fluid/13 hr.

Swb/4 WPH, 32 @ 3132-48 1/2

1000 A 3190-3202, 2000 A,

3132-48 1/2, FU 1000' fluid/13

Swb/40 BP/1 hr., 3/4 oil

Swb/10 BOPH.

P/est. 75 BOPD \neq 20% wtr.

COMPLETE

66935

LORD 111 20M 80-4334-D