

508 East Murböck
Wichita, Kansas

JAN 4 1969

SE NW SE, 1-9S-30W
Sec. T. R.

15-179-20170

CONTRACTOR'S WELL LOG

OWNER: ABERCROMBIE DRILLING, INC.
CONTRACTOR: ABERCROMBIE DRILLING, INC.
WELL NAME: MEIER #1
LOCATION: SE NW SE, SEC. 1-9S-30W
SHERIDAN COUNTY, KANSAS
COMMENCED: DECEMBER 11, 1968
COMPLETED: DECEMBER 20, 1968

Drilled 328' of 9" surface hole and set 7" casing @315 w/115 ex. Sunset cement.
Cement circulated. Plug was down at 10:00 p.m., 12-11-68.
Dry & Abandoned.

0	100	Clay & Shale
100	665	Shale
665	1400	Shale & Shells
1400	1540	Dakota Sand
1540	2220	Shale
2220	2355	Sand
2355	2546	Shale
2546	2580	Anhydrite
2580	3000	Shale
3000	3110	Lime & Shale
3110	3330	Shale & Lime
3330	3880	Lime & Shale
3880	3995	Shale & Lime
3995	4250	Lime
	4250	Rotary Total Depth

FORMATION SAMPLE TOPS

ELEVATION

Top/Anhydrite	2546	(+ 368)	2914 K. B.
Howard	3668	(- 754)	2912 D. F.
Topeka	3749	(- 835)	2906 G. L.
Heebner	3964	(-1050)	
Toronto	3987	(-1073)	
Lansing	4001	(-1087)	
Base/K. C.	4249	(-1335)	

STATE OF KANSAS)

COUNTY OF SEDGWICK)

SS

L. Abercrombie, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the MEIER #1, SE NW SE, Sec. 1-9S-30W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

By: *L. J. Abercrombie*