

MAR 6 1971

CONTRACTOR'S WELL LOG

2-9-30W
C NW NE

15-179-20167

OWNER:

CONTRACTOR:

FARM NAME:

LOCATION:

GEOLOGIST:

COMMENCED:

COMPLETED:

Abercrombie Drilling, Inc.

Abercrombie Drilling, Inc.

Calverley #1

C NW NE, Sec. 2-9S-30W

Sheridan County, Kansas *Elev. 2936' KB*

Jack K. Wharton

December 3, 1968

December 11, 1968

Day/BKC

0	150	Clay & Sand
150	226	Rock
226	339	Shale
339	780	Shale & Shells
780	1428	Shale
1428	1454	Sand
1454	2190	Shale
2190	2370	Sand
2370	2566	Shale (Red Bed)
2566	2600	Anhydrite
2600	2918	Shale
2918	3070	Shale & Lime
3070	3700	Lime & Shale
3700	3918	Lime
3918	4005	Lime & Shale
4005	4150	Lime
4150	4165	Lime & Chert
4165	4285	Lime
	4285	Rotary Total Depth

Drilled 329' of 9" surface hole and set 7" casing @326' w/100 sx. Sunset cement.
Cement circulated. Plug was down at 1:30 a.m., 12-3-68.
Dry & Abandoned

ELECTRIC LOG TOPS

<i>Anhydrite</i> 2566	
Howard	3682 (- 746)
Topeka	3764 (- 828)
Heebner	3977 (-1041)
Toronto	4000 (-1064)
Lansing	4014 (-1078)
B/K.C.	4261 (-1325)
E.L.T.D.	4285 (-1349)

ELEVATION

2936 K. B.
2934 D. F.
2928 G. L.

STATE OF KANSAS)

) SS

COUNTY OF SEDGWICK)

A. L. Abercrombie, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the #1 CALVERLEY, NW NE, Sec. 2-9S-30W, Sheridan County, Kansas, as reflected by the files.