

OPERATOR:	Chapman Exploration
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Boeger #1
LOCATION:	C SW SW NW Section 32-9S-30W Sheridan County, Kansas
SPUD DATE:	June 9, 1978
COMPLETION DATE:	June 13, 1978

0	1813	Sand & shale
1813	2221	Shale & sand
	2221	Rotary Total Depth

Spud hole at 1:30 a.m., June 9, 1978. Drilled 330' of 12¼" hole. Ran 8 joints of 8-5/8" surface casing, 28#. Set at 327.01 with 225 sacks common cement, 2% Gel, 3% CaCl. Cement did circulate. Job complete at 8:00 a.m., June 9, 1978.

T.D. 2221'. Ran 60 joints of 4½", 10½# casing. Set at 2221' with 500 sacks of 50/50 posmix, 6% gel, Sun Cement. Job complete at 8:15 a.m., June 13, 1978.

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Boeger #1, C SW SW NW Section 32-9S-30W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge,
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 28th day of June, 1978.

Sandra Richman
Sandra Richman, Notary Public



My commission expires July 21, 1979.