


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

DOLOCO EXPLORATION TRUST-
Company- MURFIN DRILLING CO.
Farm- B. Leak No. 1

SEC. 1 T. 9 R. 33 W
C NW NW

Total Depth. 4769'
Comm. Comp.
Shot or Treated.
Contractor. Murfin Drig.
Issued. 11-23-63

County Thomas
KANSAS



Elevation. 3123' GL

Production. Dry

CASING:

1st hole 8 5/8" 267' cem w/ 235 sx
2nd hole 8 5/8" 280' cem w/ 250 sx

Figures Indicate Bottom of Formations.

FIRST HOLE

Comm: 6-30-63 Comp: 7-7-63

shale	80
sand	225
shale	1750
shale & sand	2160
shale-lime, hard	
sand	2355
sand- shale	2465
red bed	2719
anhydrite	2749
shale & sand	2981
shale	3100
shale-lime	3225
shale	3400
lime- shale	3595
shale & lime	3655
lime- shale	4080
lime	4282

lost hole at this point, did not ~~old~~ rig.
but we did drill a new hole right next
to lost hole.

SECOND HOLE

Comm: 7-13-63 Comp: 7-23-63

cemeent	310
shale	1310
shale- sand	2355
Gyp	2383
shale & sand	2725
anhydrite	2754
shale & sand	2836
shale lime	3425
lime- shale	3528
shale- lime	3695
lime	3770
shale- lime	4060
lime	4769 RTD
Total Depth	

TOPS: SMP

Topeka	3847
Heebner	4082
Toronto	4099
Kansas City	4118
Base Kansas City	4428
Cherokee	4552
Mississippi	4722