

11/23/85  
KCC  
Ind

SIDE ONE

STATE CORPORATION COMMISSION OF KANSAS  
OIL & GAS CONSERVATION DIVISION

WELL COMPLETION OR RECOMPLETION FORM  
ACO-1 WELL HISTORY **CONFIDENTIAL**

DESCRIPTION OF WELL AND LEASE

Operator: License # 5063  
Name Energy Exploration  
Address 1002 So. Broadway  
City/State/Zip Wichita, KS 67211

Purchaser: N/A

Operator Contact Person Brad D. Lehl  
Phone (316) 267-7336

Contractor: License # 5063  
Name Energy Exploration

Wellsite Geologist Ralph White  
Phone (316) 685-3296

Designate Type of Completion

- New Well
- Re-Entry
- Workover
- Oil
- Gas
- Dry
- SWD
- Inj
- Other (Core, Water Supply etc.)
- Temp Abd
- Delayed Comp.

If **OWNO**: old well info as follows:

Operator  
Well Name N/A  
Comp. Date Old Total Depth

WELL HISTORY

Drilling Method:

- Mud Rotary
- Air Rotary
- Cable

8/15/85 8/22/85 8/23/85  
Spud Date Date Reached TD Completion Date  
4750' N/A  
Total Depth PBTD

Amount of Surface Pipe Set and Cemented at 384' feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set feet  
If alternate 2 completion, cement circulated from N/A feet depth to w/SX cmt

API NO. 15-192-20,364 28-9-33W  
County Thomas  
NW NE SE Sec 28 Twp 9S Rge 33  East  West


2310 Ft North from Southeast Corner of Section  
990 Ft West from Southeast Corner of Section  
(Note: Locate well in section plat below)

Lease Name HERBEL "B" Well # 1

Field Name HERBEL

Producing Formation N/A

Elevation: Ground 3157' 3162'  
Section Plat



SIP 2 3 1985

Geological Column  
BRANCA

WATER SUPPLY INFORMATION

Disposition of Produced Water:  Disposal  Repressuring  
Docket #

Questions on this portion of the ACO-1 call:  
Water Resources Board (913) 296-3717

Source of Water:  
Division of Water Resources Permit #

Groundwater 2420 Ft North from Southeast Corner  
(Well) 990 Ft West from Southeast Corner of  
Sec 28 Twp 9S Rge 33  East  West

Surface Water Ft North from Southeast Corner  
(Stream, pond etc) Ft West from Southeast Corner  
Sec Twp Rge  East  West

Other (explain) (purchased from city, R.W.D. #)

INSTRUCTIONS: This form shall be completed in duplicate and filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 90 days after completion or recompletion of any well. Rule 82-3-130 and 82-3-107 apply.

Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form. See rule 82-3-107 for confidentiality in excess of 12 months. One copy of all wireline logs and drillers time log shall be attached with this form. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

SIDE TWO

Operator Name Energy Exploration Lease Name HERBEL "B" Well # 1

Sec 28 Twp 9S Rge 33 East West County Thomas

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken [X] Yes [ ] No
Samples Sent to Geological Survey [X] Yes [ ] No
Cores Taken [ ] Yes [X] No

Formation Description [X] Log [X] Sample

DST #1 4240-4315, 30-60-30-30, Rec. 10' M & scum oil, IHP 2170, IFP 11-11, ISIP 224, FFP 22-22, FSIP 44, FHP 2091, Temp. 127'.
DST #2 4618-4660 (Cher. Jhn.) 30-30-30-30, Rec. 2' M, IHP 2294, IFP 22-22, ISIP 22, FFP 22-22, FSIP 22, FHP 2304, Temp. 132'.
DST #3 4655-4700 (Cher. Sand/Cong.) 30-30-30-30, Rec. 20' M show oil on tool, IHP 2607, IFP 33-33, ISIP 336, FFP 33-33, FSIP 100, FHP 2562, Temp. 132'.

Table with 3 columns: Name, Top, Bottom. Rows include Anhydrite, Heebner, Lansing, Stark Shale, BKC, Marmaton, Pawnee, Ft. Scott, Cher. Sh., Cher. Jhn., Cher. Sand, Mississippi, T.D.

CASING RECORD [X] New [ ] Used
Report all strings set-conductor, surface, intermediate, production, etc.
PERFORATION RECORD
Acid, Fracture, Shot, Cement Squeeze Record
TUBING RECORD
Date of First Production
Producing Method