

State Geological Survey
WICHITA BRANCH

S. 30 T. 9 R. 35 W E
W

County Thomas

Donald C. Slawson

200 Douglas Building Wichita, Kansas 67202

1

Siruta 'B'

2340'

feet from (N) (S) line

220'

feet from ~~XX~~ (E) (W) line

Slawson Drilling Co., Inc.

Don Moore

September 22, 1978


4930'

N/A

October 1, 1978

N/A

640 Acres
N



Locate well correctly

Elev.: Gr. 3356

DF 3359 KB 3361

Report of all strings set—surface, intermediate, production, etc.

LINER RECORD

PERFORATION RECORD

~~TUBING RECORD~~

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

INITIAL PRODUCTION

Date of first production

Producing method (flowing, pumping, gas lift, etc.)

**RATE OF PRODUCTION
PER 24 HOURS**

Oil

Gas

Water

Gas-oil ratio

CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator DONALD C. SLAWSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Siruta 'B'	Dry Hole
S 30 T 9 R 35 W E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
LOG TOPS				
0 - 363 Surface hole			ANH 2823	(+536)
363 - 1380 Shale and shells			B/ANH 2851	(+510)
1380 - 2090 Shale and sand			TOP 3922	(-561)
2090 - 2822 Shale and shells			HEEB 4126	(-765)
2822 - 2855 Anhydrite			LANS 4175	(-814)
2855 - 2877 Shale and shells			MN CK 4305	(-944)
2877 - 4086 Shale and lime			STK 4392	(-1031)
4086 - 4195 Lime			HPKY 4427	(-1066)
4195 - 4288 Shale and lime			B/KC 4450	(-1089)
4288 - 4561 Lime			MARM 4474	(-1113)
4561 - 4656 Shale and lime			ALTA 4506	(-1145)
4656 - 4704 Lime			PAW 4572	(-1211)
4704 - 4835 Lime and shale			U/CHER 4628	(-1267)
4835 - 4930 Lime			L/CHER 4653	(-1302)
4930 RTD			JH ZN 4705	(-1344)
			MOR 4761	(-1400)
			MISS 4814	(-1453)
			LTD 4927	(-1566)
DST #1 3891-3960 (HOW-TOP) 30-60-45-75, SBTO, Rec. 470' MSW. IFP 69-172#, ISIP 1100#, FFP 172-258#, FSIP 1083#, 121°.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature R.J. THATCHER - Engineer Title December 15, 1978 Date
---------------	---

58869

WELL LOG

30-9-35W

OPERATOR: Donald C. Slawson
200 Douglas Building
Wichita, Kansas 67202

LEASE: #1 Siruta 'B'
Approx NW NW SW of Sec. 30-9-35W
Thomas County, Kansas

CONTRACTOR: Slawson Drilling Co., Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: September 22, 1978

COMPLETED: October 1, 1978

CASING: Surface - 8 5/8" @ 357' w/250 sx 60/40 poz

0 -	363	Surface hole
363 -	1380	Shale and shells
1380 -	2090	Shale and sand
2090 -	2822	Shale and shells
2822 -	2855	Anhydrite
2855 -	2877	Shale and shells
2877 -	4086	Shale and lime
4086 -	4195	Lime
4195 -	4288	Shale and lime
4288 -	4561	Lime
4561 -	4656	Shale and lime
4656 -	4704	Lime
4704 -	4835	Lime and shale
4835 -	4930	Lime
4930		RTD

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

I, R.J. THATCHER, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Siruta 'B' test.