

MC CLELLAND

Form 113 50M 4-49—47450-D

State Kansas County Rooks (RI)

Sec. 8 Twp. 9 Rng. 19w Elev. 2062

Company C. Wentworth & Sons

Well No. 2 Name Ziebler

Location NE SE SE

Feet from lines: N. S. E. W.

Spud 9-2-49 Completed 10-19-49

T. D. 3559 Casing 5" 3534

PB 3549

Comp. Perf. 3530-38

Pay 3530-49 in Arb.

I. P. 90 BOPD / tr. wtr.

Choke T. P. C. P.

G. O. R. Grvty.

DATE	REMARKS
10-19-49	Anhy. 1485, Heeb. 3224, Tor. 3246, Lans. 3265, Gel. 3508, Arb. 3534, sh. dead oil 3274-79, poor por. stn., no odor 3293-3304,

DATE	REMARKS
DVIL	DST 3268-3313, open 1 hr., rec. 128' O & GCM, DST 3335-51, open 1 hr., rec. 1850' fluid, 240' heavy OGM, 830' oil & Muddy wtr., 780' wtr., tr. oil. BHP 1025#, RTD 3537, VSSFO Ran Schlum. DP DD SO 3547, DD 3559 sh. wtr. PP 3547, 1500 A, P/est. 3 BOPH + 10% wtr../8, decl. 1 BOPH Perf. 3530-38, 3000 A, P/6 BOPH, tr. wtr./48, Grav. 27 CO 3549 P/3 $\frac{1}{2}$ BOPH 3547 $\frac{1}{2}$ -49 P/est. 90 BOPD + tr. wtr.
	COMPLETE
	E08229