


20-9-8W
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas 15-123-00011

Company- IRVING NAGEL & NATIONAL DRILG. CO.
Farm- Schneider No. 1

SEC. 20 T. 9 R. 9W
C SW NW

Total Depth. 4126'
Comm. 12-30-61 Comp. 1-9-61
Shot or Treated.
Contractor. National Drilg. Co.
Issued. 12-2-61

County Mitchell
KANSAS



CASING:
8 5/8" 195' cem w/150 sx.

Elevation. 1659' DF

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	25
shale & shells	195
shale & sand	488
shale & shells	550
sand	600
red bed & shale	1190
shale & shells	1350
lime & shale	1925
shale & shells	2412
shale & lime	2475
lime	2500
lime & shale	2848
lime	3140
shale & lime	3450
lime & chert	3510
Mississippian	3580
lime & shale	3830
lime	4005
lime & shale	4070
lime	4126 RTD
Total Depth	

TOPS: ELECTRIC	
Salt	1060 to 1130
Ft. Riley	1475
Howard	2441
Topeka	2476
Heebner	2720
Lansing	2800
Base Kansas City	3139
Cherokee Shale	3276
Mississippi	3412
Kinderhook	3624
Hunton	3670
Maquoketa	3708
Viola	3794
Simpson	4000
Arbuckle	4067