

STATE OF KANSAS
CORPORATION COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21,195 2/228-0000

RECEIVED
NOV 05 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Gagnebin

WELL NUMBER 1-11

990 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 11 TWP. 24S RGE. 9W (E) or (W)

COUNTY Reno

Date Well Completed _____

Plugging Commenced 10-10-03

Plugging Completed 10-15-03

LEASE OPERATOR CORSAIR ENERGY, LC

ADDRESS 914 E. Douglas Wichita, Kansas 67202

PHONE (316) 267-7779 OPERATOR'S LICENSE NO. 5058

Character of Well Gas

(i.e., Gas, D&A, SWD, Input, Water Supply Well)

Is a plugging proposal was approved on _____ (date)

By Jack Luthi (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4214'

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	171'	None
				7"	4212.5'	2419'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each side. Plugged off bottom with sand to 3500' and 7 sacks cement. Shot pipe loose @2419', pulled up to 1400', pumped 15 sacks gel, 50 sacks cement and 100# hulls, pulled up to 850', pumped 50 sacks cement and 100# hulls, pulled up to 250' and circulated 125 sacks cement, topped off with 5 sacks 60/40 pos. 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Corsair Energy LC

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 4th day of November, 20 03

[Signature]
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 12/31/04

Form 9
Revised 05-