

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20303-00-00
Spot: E2NWNW Sec/Twnshp/Rge: 8-15S-41W
. 4480 feet from S Section Line, 4330 feet from E Section Line
Lease/Unit Name: COX Well Number: 1-8
County: WALLACE Total Vertical Depth: 5120 feet

Operator License No.: 31120
Op Name: PELICAN HILL OIL & GAS, INC.
Address: 1401 N EL CAMINO REAL, STE 207
SAN CLEMENTE, CA 92672

Surface Casing Size: 8.625 feet: 375

\$ 166⁴⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/31/2003 12:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ED MCKENNA Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed
Plugging
Method:

Ordered 200 sxs cement.

Plugging Proposal Received By: ROGER MOSES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/31/2003 4:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 375'.
1st. Plug at 2780' w/25 sxs cement.
2nd. Plug at 1725' w/100 sxs cement.
3rd. Plug at 425' w/40 sxs cement.
4th. Plug at 40' w/10 sxs cement.
15 sxs in rathole.
10 sxs in mousehole.
Total of 200 sxs 60/40 pozmix - 6% gel with 1/4# flocel per sack - with 8 5/8" wiper plug.

RECEIVED
NOV 06 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

110

Signed Roger Moses
(TECHNICIAN)

INVOICED
DATE 11-6-03
INV. NO. 2004060746

Form CP-2/3

NOV 03 2003