

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21388-00-00  
Spot: SESENW Sec/Twnshp/Rge: 14-26S-16W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: WICHSER Well Number: 1  
County: EDWARDS Total Vertical Depth: 4430 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: PO BOX 8647  
WICHITA, KS 67208

Production Casing Size: 4.5 feet: 4180 WITH 100 SX CMT  
Surface Casing Size: 8.625 feet: 429 WITH 150 SX CMT

#143<sup>98</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2003 10:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4000' & 4 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/27/2003 12:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 4136'. PERFS AT 4052-58'. SANDED TO 4001' & 4 SX CMT. RIPPED PIPE @ 2400' & WELL BLEW IN. PUMPED 50 SX CMT & DISPLACED TO 2300'. MAXIMUM PRESSURE 900 PSI. SHUT IN PRESSURE 800 PSIG (WAS SHUT IN OVER WEEKEND). RIPPED PIPE @ 2220'. PULLED TO 1200' & PUMPED 15 SX GEL & 50 SX CMT. PULLED TO 450' & PUMPED 50 SX CMT. PULLED TO 40' & PUMPED 20 SX CMT.

RECEIVED  
NOV 06 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2220' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

11-6-03

2004060744

Form CP-2