

3 120349

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-049-21,405-00-00  
NE NE NW Sec/Twp/Rge 34-29-9E  
5115 feet from south section line  
2805 feet from east section line #76 38

TECHNICIAN'S PLUGGING REPORT

Operator License # 5177  
Operator: SUERTE OIL COMPANY  
Name & P. O. BOX 725  
Address HOWARD, KS 67349

Lease/Well# PERKINS # 1  
County ELK  
Well Total Depth 2350 feet  
Production Pipe: 4.5" Size Feet 2346  
Surface Casing: 8 5/8" Size Feet 69  
AB oil well X Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: BRADEN PET. & WELL PULLING CO. Lic. # 32475

Address: P. O. BOX 282, BURDEN, KS 67019

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 5 Month: \_\_\_\_\_ 8 2003

Plugging proposal received from: MAURICE PERKINS

Company Name: SUERTE OIL CO. Phone: 620-374-2000

Were: TO DUMP-BAIL SAND & CEMENT, THEN PUMP CEMENT FOR BOTTOM, MIDDLE, & TOP PLUGS.

Plugging Proposal Received by: RON ROWE

Plugging attended by Agent: All \_\_\_\_\_ Part X None \_\_\_\_\_

TECHNICIAN

Operations Completed: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 6 Month: \_\_\_\_\_ 8 2003

Actual Plugging Report: DUMP-BAILED/SANDED BACK TO 2200', THEN 5 SACKS CEMENT

ON SAND. SET/BUILD SAND BRIDGE @ 1450-1400', THEN 5 SACKS CEMENT ON SAND.

SHOT-OFF & PULLED 1200' OF 4.5" CASING. RAN 1" TO 450' & PUMPED/CIRCULATED CEMENT

TO SURFACE. PULLED 1" AND TOPPED-OFF WELL.

USED TOTAL OF 145 SACKS CEMENT.


Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: \_\_\_\_\_

RON ROWE

TECHNICIAN

  
TECHNICIAN

RECEIVED

OCT 29 2003

KCC WICHITA

INVOICED

DATE 11-6-03  
NO. 2004060749