

3 120349

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-049-21,889-00-00
NE NW NW Sec/Twp/Rge 34-29-9E
4980 feet from south section line
4590 feet from east section line *\$76⁰⁵*

TECHNICIAN'S PLUGGING REPORT

Operator License # 5177
Operator: SUERTE OIL COMPANY

Lease/Well# PERKINS # 5
County ELK
Well Total Depth 2340 feet

Name & P. O. BOX 725

Production Pipe: 4.5" Size Feet 2340

Address HOWARD, KS 67349

Surface Casing: 7 5/8" Size Feet 452

AB oil well Gas Well SWD Well/ Input Well D & A

Other well as hereinafter indicated: _____

Plugging Contractor: BRADEN PET. & WELL PULLING CO. Lic. # 32475

Address: P. O. BOX 282, BURDEN, KS 67019

Company to plug at: Hour: _____ Day: 7 Month: 8 2003

Plugging proposal received from: MAURICE PERKINS

Company Name: SUERTE OIL CO. Phone: 620-374-2000

Were: TO DUMP-BAIL SAND & CEMENT, THEN PUMP CEMENT FOR BOTTOM, MIDDLE, & TOP PLUGS.

Plugging Proposal Received by: RON ROWE

Plugging attended by Agent: All Part None TECHNICIAN

Operations Completed: Hour: _____ Day: 11 Month: 8 2003

Actual Plugging Report: DUMP-BAILED/SANDED BACK TO 2240', THEN 5 SACKS CEMENT

ON SAND. SET/BUILD SAND BRIDGE @ 1450-1400', THEN 5 SACKS CEMENT ON SAND.

SHOT-OFF & PULLED 720' OF 4.5" CASING. RAN 1" TO 500' & PUMPED/CIRCULATED CEMENT

TO SURFACE. PULLED 1" AND TOPPED-OFF WELL.

USEE TOTAL OF 105 SACKS CEMENT.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: *Ron Rowe*
RON ROWE
TECHNICIAN *Ru*

INVOICED
DATE 11-6-03
SER. NO. 2004010749

RECEIVED
OCT 29 2003
KCC WICHITA