

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-20430-00-01
Spot: NWNENW Sec/Twnshp/Rge: 29-34S-12E
4731 feet from S Section Line, 3907 feet from E Section Line
Lease/Unit Name: WINCHELL Well Number: 47
County: CHAUTAUQUA Total Vertical Depth: 1138 feet

Operator License No.: 31302
Op Name: JONES & BUCK DEVELOPMENT
Address: PO BOX 68 304 E. MAIN
SEDAN, KS 67361

Production Casing Size: 4.5 feet: 1128
Surface Casing Size: 7 feet: 21

36⁹⁹

Well Type: EOR UIC Docket No: E16971.6 Date/Time to Plug: 07/25/2003 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S INC. Phone: (620) 725-5538

Proposed Plugging Method: TO PUMP CEMENT FOR BOTTOM AND TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 07/25/2003 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

BULLHEAD PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG, THEN GEL SPACER AND PRESSURED TO 700#. RAN 1" HYDRIL INSIDE 4.5" CASING TO 350' AND PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" AND TOPPED OFF WELL. USED TOTAL OF 45 SACKS CEMENT AND 2 SACKS GEL.

RECEIVED
KCC District #3

NOV 4 2003

RECEIVED
NOV 06 2003
KCC WICHITA

Chautauque, KS

Remarks:

Plugged through:

District: 03

Signed

Ron Rowe

(TECHNICIAN)

INVOICED

DATE 11-6-03
BY NO. 2004060742