

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,823-0000

LEASE NAME Bentley

WELL NUMBER 2

1,650 Ft. from S Section Line

1,800 Ft. from E Section Line

SEC. 13 TWP. 16 RGE. 28 (E) or (W)

COUNTY Lane

Date Well Completed 10-30-03

Plugging Commenced 10-30-03

Plugging Completed 10-30-03

LEASE OPERATOR CARMEN SCHMITT, INC.

ADDRESS PO BOX 47, GREAT BEND, KS 67530

PHONE (620) 793-5100 OPERATORS LICENSE NO. 6569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-30-03 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,573'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	219'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Push plug to 2,100', pump 50 sax cement on plug thru drill pipe; push plug to 1,300', pump 50 sax cement on plug thru drill pipe; push plug to 650', pump 50 sax cement on plug thru drill pipe; push plug to 250', pump 50 sax cement on plug thru drill pipe; push plug to 40'; dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CARMEN SCHMITT, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 3rd day of November, XDXK2003

My Commission Expires: _____



Ruth Phillips
Notary Public



Shields


WELL LOG

15-101-21823-00-00

Russell, Kansas

Operator: Carmen Schmitt, Inc.
 Well: Bentley #2
 Commenced: October 21, 2003
 Completed: October 31, 2003
 Contractor: Shields Drilling Co.

Well Description: 1,650' FSL,
 1,800' FEL,
 SE/4 Sec. 13-16S-28W
 Lane County, KS



Elevation: 2,656' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	219'	Cmtd. w/150 sax

RECEIVED

NOV 06 2003

KCC WICHITA

..... Figures Indicate Bottom of Formations

Sand & shale	1,120'
Shale	1,490'
Shale & sand	2,059'
Anhydrite	2,097'
Shale	3,490'
Shale & lime	4,049'
Lime	4,141'
Lime & shale	4,150'
Lime	4,232'
Lime & shale	4,320'
Lime	4,470'
Lime & shale	4,562'
Lime	4,573' RTD