

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21100-00-00  
Spot: NENW Sec/Twnshp/Rge: 35-34S-30W  
630 feet from N Section Line, 1980 feet from W Section Line  
Lease/Unit Name: CIMARRON Well Number: 1-35  
County: MEADE Total Vertical Depth: 6430 feet

Operator License No.: 30604  
Op Name: RAYDON EXPLORATION, INC.  
Address: 9400 N. BROADWAY #400  
OKLAHOMA CITY, OK 73114

Conductor Pipe Size: 20 feet: 40 5 YARDS 10 SX GROUT  
Production Casing Size: 4.5 feet: 6420 WITH 200 SX CMT  
Surface Casing Size: 8.625 feet: 1650 WITH 555 SX CMT  
\$208.98

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/07/2003 10:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS WITH 20 SX CMT. PLUG AT 1675' WITH 50 SX CMT. PLUG AT 550' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/07/2003 2:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 6361'. PERFS AT 5978-6004'. PUMP 300# HULLS & 20 SX CMT ON BOTTOM. LOAD HOLE WITH MUD. 1ST PLUG AT 1675' WITH 50 SX CMT. 2ND PLUG PULL TO 550' & SPOT 30 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

RECEIVED  
NOV 12 2003  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2802' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICE

DATE

11-12-03

W. NO.

2004060768

Form CP-23