

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20360-00-00
Spot: W2NWNE Sec/Twnshp/Rge: 6-35S-25W
660 feet from N Section Line, 2310 feet from E Section Line
Lease/Unit Name: THEIS Well Number: 1-6
County: CLARK Total Vertical Depth: 6350 feet

Operator License No.: 4951
Op Name: CLAASSEN OIL AND GAS, INC.
Address: P.O. BOX 417
ESTES PARK, CO 80517

Conductor Pipe Size: 20 feet: 39 4 YARDS ~~#206~~ 38
Production Casing Size: 4.5 feet: 6342 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 736 WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/22/2003 9:15 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 20 SX CMT & 100# HULLS. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/22/2003 11:30 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 6160'. PERFS AT 5856-62'. PUMP 20 SX CMT & 100# HULLS. LOAD HOLE WITH MUD. 1ST PLUG PULL TO 1000' & SPOT 50 SX CMT. 2ND PLUG PULL TO 750' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL THROUGHOUT JOB.

RECEIVED
NOV 12 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2500' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Middleton
(TECHNICIAN)

INVOICED
DATE 11-12-03
INV. NO. 2004060766