

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20379-00-00
Spot: NESWSWNE Sec/Twnshp/Rge: 25-24S-36W
2190 feet from N Section Line, 2300 feet from E Section Line
Lease/Unit Name: ESFIELD Well Number: 1-2
County: KEARNY Total Vertical Depth: 2935 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 12600 NORTHBOROUGH, SUITE 250
HOUSTON, TX 77067

Production Casing Size: 5.5 feet: 2934 WITH 700 SX CMT
Surface Casing Size: 8.625 feet: 500 WITH 300 SX CMT

\$95.39

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/29/2003 10:00 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS & 25 SX CMT. PLUG AT 1850' WITH 50 SX CMT. PLUG AT 700' WITH 80 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/29/2003 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2887'. PERFS AT 2700-2811'. PUMP 500# HULLS WITH 25 SX CMT. DISPLACE TO BOTTOM WITH MUD. PRESSURE TO 500 PSIG & SHUT IN. 1ST PLUG 1ST PLUG CIRCULATE HOLE WITH MUD & PUMP 20 SX CMT AT 900'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 720'. CIRCULATE HOLE & PUMP 80 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
NOV 10 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 900' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
NOV - 5 2003
KCC Dodge City

Signed

Jim Holland

(TECHNICIAN)

INVOICED
11-12-03
2004060762

Form CP-203