

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21326-00-00  
Spot: SWSW Sec/Twnshp/Rge: 8-31S-34W  
660 feet from S Section Line, 660 feet from W Section Line  
Lease/Unit Name: HOME ROYALTY Well Number: 1-8  
County: SEWARD Total Vertical Depth: 5820 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

Production Casing Size: 5.5 feet: 5687 WITH 525 SX CMT  
Surface Casing Size: 8.625 feet: 1705 WITH 725 SX CMT

#189 15

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2003 12:30 PM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PUMP MUD SPACER TO 1750'. PUMP CMT FROM 1750' TO SURFACE. PRESSURE CHECK. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE  
Date/Time Plugging Completed: 10/30/2003 2:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: JIM HOLLAND

Actual Plugging Report:


PERFS AT 5542-5584'. DV TOOL @ 3000' WITH 350 SX CMT. PUMP 300# HULLS WITH 25 SX CMT. FOLLOW BOTTOM PLUG WITH 85 BBL MUD SPACER TO 1750'. PUMP 132 SX CMT FROM 1750' TO SURFACE. PRESSURE TO 700 PSIG & SHUT IN. PUMP 1 SX CMT DOWN BACKSIDE. PRESSURE TO 300 PSIG & SHUT IN.

RECEIVED  
NOV 10 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II  
(TECHNICIAN)

INVOICED  
DATE 11-10-03  
WEL NO 2004060766

Form CP-2/B