

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21097-00-00
Spot: S2NWSE Sec/Twnshp/Rge: 21-32S-30W
1680 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: FOX Well Number: 1-21
County: MEADE Total Vertical Depth: 3466 feet

Operator License No.: 30604
Op Name: RAYDON EXPLORATION, INC.
Address: 9400 N. BROADWAY #400
OKLAHOMA CITY, OK 73114

Conductor Pipe Size: 20 feet: 40 WITH 6 SX GROUT
Production Casing Size: 4.5 feet: 3443 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 706 WITH 255 SX CMT

\$ 112.05

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/03/2003 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 100# HULLS WITH 15 SX CMT. PRESSURE TEST. PLUG AT 1600' WITH 40 SX CMT. PLUG AT 725' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/04/2003 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3404'. PERFS AT 2836-40'. CIBP @ 3132'. 11/03/03: PUMP 100# HULLS WITH 15 SX CMT. DISPLACE WITH MUD. PRESSURE TO 500 PSIG & SHUT IN. SHOOT CASING OFF AT 2315'. 11/04/03: 1ST PLUG PULL OUT OF HOLE TO 1600'. PUMP MUD UNDER PRESSURE (700 PSIG). DID NOT CIRCULATE. PUMP 40 SX CMT. (EQUIPMENT BREAKDOWN). DISPLACE WITH MUD. PIPE STUCK. SHOOT OFF AT 1016'. 2ND PLUG PULL OUT OF HOLE TO 725'. CIRCULATE HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
NOV 10 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1730' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
NOV - 5 2003
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 11-12-03
INV. NO. 2004060763

Form CP-2/3