

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21445-00-00
Spot: SWSE Sec/Twnshp/Rge: 5-25S-16W
660 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: JULIAN Well Number: 1-5
County: EDWARDS Total Vertical Depth: 4420 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 N.W. 112TH
OKLAHOMA CITY, OK 73162

Production Casing Size: 4.5 feet: 4416 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 332 WITH 225 SX CMT

\$14365

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2003 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: SAND TO 4294' & 4 SX CMT. PLUG AT 1100' WITH 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/06/2003 3:58 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PERFS AT 4308-4364'. COMPANY LEFT IN HOLE CASING KNIFE, STEM, & JARS @ 2600'. SANDED TO 4294' & 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1100' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
NOV 10 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2400' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 11-12-03

INV. NO. 2004060760

Form C-273