

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25072-00-00
Spot: W2W2SW Sec/Twnshp/Rge: 17-11S-20W
1305 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: ROSEMARY Well Number: 17-1X
County: ELLIS Total Vertical Depth: 3800 feet

Operator License No.: 32511
Op Name: IMPERIAL AMERICAN OIL CORPORATI
Address: 303 N. CARROLL BLVD., #214
DENTON, TX 76201

Production Casing Size: 5.5 feet: 3795 w/150 sxs cmt
Surface Casing Size: 8.625 feet: 238 w/160 sxs cmt

#123⁵⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/27/2003 12:00 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: MIKE STANTON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-4459

Proposed Plugging Method: Ordered 200 sxs cement and 500# hulls.
Perfs at 1250' - 1254'; 666' - 670'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/27/2003 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 238' w/160 sxs cement. 5 1/2" casing at 3795' w/150 sxs cement.
Port collar at 1550' w/200 sxs cement.
Ran tubing to 1552' - circulated with 120 sxs cement and 300# hulls.
Pulled tubing - squeezed 5 1/2" with 10 sxs cement and 200# hulls.
Max. P.S.I. 900#. S.I.P. 500#.
Visual inspection of annulus - full.
Total of 130 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
NOV 06 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: TBG

District: 04

JD

Signed Roger L Moses
(TECHNICIAN)

INVOICED

DATE 11-6-03

WIC. NO. 3004060740

NOV 03 2003

IMPERIAL AMERICAN OIL CORP
WICHITA KS 67212

17-11S-20W
15'S, C W/2 W/2 SW

#17-1X ROSEMARY

site 6 N & 9-3/4 W OF HYACINTH KS city: ELLIS API 15-051-25072
contr: MURFIN DRILLING #8 field: NICHOLSON NE EXT (1/2+ NW;
geol: RANDALL KILIAN INFLD DISC)

fr	spd	drig	card	last
date 12/22/2000	date 12/26/2000	comp 01/03/2001	issued 04/09/2001	revised 04/09/2001

ELV: 2118 KB, 2113 GL LOG	
tops.....	depth/datum
ANH.....	1552 +566
TOP.....	3155 -1037
LANS.....	3407 -1289
ARB.....	3702 -1584
LTD.....	3798 -1680
RTD.....	3800 -1682

IP status
OIL, P 10 BOPD, NW, LKC 3587-3602 OA, 01/21/2001
CSG: 8-5/8" 238 / 160 SX (ALT 2), PROD CSG NA, MULTI
STAGE COLLAR AT 1558
COMMENT: RIG SKID JOB; REPLACES #17-1 ROSEMARY,
LOST HOLE (FR 12/18/2000, OPER: SAME, API 15-051-25071)
NO CORES
4 DSTS TAKEN - DETAILS NA
TRGT ZN: LKC, ARB (OIL), PTD 3900 (ARB), MICT - CO, PF
(ARB) 3704-3708, W / 4 SPF, NON-PROD, NAT, SET CIBP AT
3680, PF (LKC) 3587-3589, 3600-3602, W / 4 SPF, SWB DWN,
SO, NAT, SET 2-7/8" TBG AT 3631, NO PKR, POP, IPP 10
BOPD, NW (GR 21), NSG, DOFP 1/21/2001 - NO OTHER INFO
AVAILABLE - TEMP COMP 4/9/2001

COPYRIGHT 2001
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS