

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04811-00-00
Spot: S2SENE Sec/Twnshp/Rge: 20-19S-13W
· 2970 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: MCKINNEY Well Number: 2
County: BARTON Total Vertical Depth: 3447 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

Production Casing Size: 5.5 feet: 3442 125 SX CMT
Surface Casing Size: 8.625 feet: 765 400 SX CMT

#112⁰³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2003 9:00 AM

Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.

Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 10/31/2003 1:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: CASE MORRIS

Actual Plugging Report:

Had cement in head.
Ran tubing to 2200'.
Circulated with 160 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
POOH.
Tied onto 5 1/2" and pumped 140 sxs cement.
Fluid circulating up in bottom of cellar.
Pumped 95 sxs cement - cement circulated.

RECEIVED
NOV 06 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

INVOICE
11-6-03
2004060743

NOV 04 2003

HONAKER DRILLING #2 MCKINNEY 20-19-13W
 S2 SE NE
 Contr. HONAKER DRLG BARTON County
 E. 1854 RE Comm. 8-20-55 Comp. 10-21-55 IP 222 BOPD

Tops	Depth	Datum
KC	3170	-1316
CONG	3403	-1549
ARB	3442	-1588
TD	3447	-1593

Casing
 8" 765
 5" 3442

CO 3447: 6 BOPH

GT BEND TWST POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS