

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
100 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-21814-00-00

LEASE NAME Seeyle

WELL NUMBER 1

2640 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 35 TWP. 15 RGE. 19W (E) or (W)

COUNTY Ellis

Date Well Completed \_\_\_\_\_

Plugging Commenced 10-20-03

Plugging Completed 10-22-03

RECEIVED  
NOV 13 2003  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR ENERGY ONE OIL OPERATION

ADDRESS 1116 E. 8th Hays, Kansas 67601

PHONE# (785) 625-5724 OPERATORS LICENSE NO. 32552

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3666'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1245'	None
				5-1/2"	3666'	2320'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 3250' and 5 sacks cement. Shot pipe loose @2320', pulled up to 1950', pumped 80 sacks cement and 300# hulls, pulled pipe up to 1330', pumped 40 sacks cement, pulled up to 650' and circulated 80 sacks cement to surface. Layed rest of pipe down and topped off with 35 sacks cement. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Energy One Oil Operations

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 11th day of November, 20 03

[Signature]  
Notary Public

My Commission Expires:



[Signature]  
Form 67  
Revised 05-