

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02941-00-00
Spot: NENENW Sec/Twnshp/Rge: 26-9S-22W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: BARBER B Well Number: 1
County: GRAHAM Total Vertical Depth: 3789 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3789 w/unknown cmt
Surface Casing Size: 8.625 feet: 240 w/200 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2003 11:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/07/2003 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 950' and 1840'.
Swaged onto 5 1/2" - mixed and pumped 250 sxs cement with 900# hulls.
Max. P.S.I. 400#. S.I.P. 200#.
Hooked up to the annulus and pumped 15 sxs cement.
Max. P.S.I. 1000#. S.I.P. 800#.

RECEIVED
NOV 18 2003
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS IRONCLAD UNIT #301. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

Form CP-273

NOV 10 2003

COMP. 3-393 MAP NO. _____ (OWWO) SEC. 26-9S-22W
 STATE Kansas COUNTY Graham LOC. NE NE NW
 OPER. Cities Service Oil Co. Wichita, Kansas FT/FR _____ LINE
 WELL #301 FARM Ironclad Unit 301 FT/FR _____ LINE
 POOL Ironclad ELEV. _____ GR. 2342 DF 2345 KB

CONT _____ GEOL. _____
 CO. _____
 INT. _____
 F.R. 3-24-64 SPUD. Old 7-17-50 COMP. 3-31-64
 TD 3789 FM. BKG PBTD.

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
	Lan	3587	-3758	100	1000A
I.P. Co. Pump: 3 BO + 23 BW/24 hrs.					

Casing Record
 8" @240' w/200 Sx.
 5" @3789' w/cem.

Data Inc.

	Old Tops:	(KB)		
Hb	3515	-1170	BKC	3773 -1428
Dodge	3536	-1191	OTD	3789 <u>OLD INFO:</u>
Lan	3551	-1206		-1444
DST #1(Lan)3580-97, Op 30', R 90' FO, 60' GCM & OCM, No press. CO, Pf. 25/3746-58(lan)1500A, \$ 1d, P 83 BO + 134 BW/16 hrs. PB 3628', Pf. 13/3587-99, 24/3591-99, 11/3587-91(Lan)1500A, \$ 1d,				

P 168 BO + 6 BW/8 hrs. CO to 3674', PBTD. Pot: 323 BOPD + 2% wtr.
 Lans 3587-3758, Completed 9-27-1950.
NEW INFO: (2-28-64) OTD 3789'; MICT, Pull T&R, CO 3764', PBTD(Old)
 FL 3570' from surf. Pf. 24/3723-31(Lan) No incr. in fluid. Treat
 pfs. 3723-31, w/1000A. T&R, POP, P 2 BO + 75 BW/20 hrs. (NPO)
 (14 B new water.) P 4 BO + 39 BW/24 hrs. Pull pump, CO, Reset pump
 P 3 BO + 29 BW/24 hrs. PO, Co. P 3 BO + 23 BW/24 hrs. (Old) Lan
 3587-3758 (New) (Lan) 3723-31, (Was CSO #1 BARBER "B") COMPLETED
 3-11-64, FIRST REPORTED & COMPLETED 3-24-64.