

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-02991-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 25-9S-22W  
2970 feet from S Section Line, 4290 feet from E Section Line  
Lease/Unit Name: GUSTAFSON Well Number: 3  
County: GRAHAM Total Vertical Depth: 3810 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3700  
Surface Casing Size: 8.625 feet: 280

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/18/2003 11:00 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 10% gel - 1000# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/18/2003 2:00 PM KCC Agent: JAY PFEIFER

**Actual Plugging Report:**

MIRU to drill out bridges.  
Hit first bridge at 12' - dropped through to 550'.  
Hit hard bridge and lost circulation - could not drill through - decided to P&A.  
POOH. Swaged onto 5 1/2" - mixed and pumped 400 sxs cement with 1000# hulls.  
Max. P.S.I. 700#. S.I.P. 200#.  
Hooked to the annulus and pumped 50 sxs cement.  
Max. P.S.I. 500#. S.I.P. 200#.


RECEIVED  
NOV 19 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

MAGNOLIA PETROLEUM #3 GUSTAFSON 25-9-22W  
 SE SW NW

Contr. TRANSIT CORP GRAHAM County

E 2362 Comm. Comp. 8-12-55 IP 106 BOPD  
 PERM PMPG

Tops	Depth	Datum
HEEB	3536	-1174
LANS	3575	-1213
1D	3810	-1148

Casing  
 9" 280  
 5" 3700  
 DST 3576-3600/1 HR, 34' SL  
 OCM, BHP 280#;  
 DST 3600-46/1 HR, 25' MUD,  
 BHP 50#;  
 PERF 20/3615-20: 1 GWP/12  
 ACID 1000: 11 BO/11 HR: ACID  
 3000: 2 BOPH/13 HR: PB 3590  
 IRONCLAD POOL 24/3576-82:  
 ACID 4000: 8  
 BO & 9 BW/24 HR


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS