

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-19337-00-01
Spot: SENESW Sec/Twnshp/Rge: 14-24S-12E
1671 feet from S Section Line, 3045 feet from E Section Line
Lease/Unit Name: SULLIVAN Well Number: W 25
County: GREENWOOD Total Vertical Depth: 1813 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN 510 HARDAGE CENTER
WICHITA, KS 67202

Production Casing Size: 6.625 feet: 1781
Surface Casing Size: 8.625 feet: 24 **\$5892**

Well Type: EOR UIC Docket No: E07558.21 Date/Time to Plug: 10/28/2003 8:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: Company: R.R.A., INC. Phone: (316) 262-3411

Proposed Plugging Method: 50' CEMENT PLUG AT 1750', 50' CEMENT PLUG AT 900', 150' CEMENT PLUG TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/31/2003 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

TUBING AND PACKER HUNG IN CASING BELOW 900', UNABLE TO RETRIEVE, SHOT CASING AT 864', RAN TUBING TO 878' AND PUMPED 60 SACKS CEMENT. SHOT CASING AT 146', PULLED CASING OUT AND RAN TUBING TO 155', PUMPED 90 SACKS CEMENT TO SURFACE.

RECEIVED
KCC District #3
NOV 17 2003 NOV 13 2003
KCC WICHITA
Shandic

Remarks: CORRECTED TO GPS LOCATION

Plugged through:

District: 03

Signed

Mike Heffern
(TECHNICIAN)

INVOICED
DATE 11-18-03
AMOUNT 2004060774