

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-20121-00-00
Spot: NESENE Sec/Twnshp/Rge: 17-25S-16E
3783 feet from S Section Line, 234 feet from E Section Line
Lease/Unit Name: LIGHT B Well Number: 3
County: WOODSON Total Vertical Depth: 1015 feet

Operator License No.: 5935

Production Casing Size: 2.875 feet: 1015

Op Name: HAAS, MARK L.

Surface Casing Size: 6 feet: 40

Address: PO BOX 23449

SHAWNEE MISSION, KS 66283

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/08/2003 9:00 AM

Plug Co. License No.: 31440

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Rcvd. from: LLOYD SLEEZER

Company: MARK L. HAAS

Phone: (913) 402-0998

Proposed
Plugging
Method:

THIS WELL CONSISTED OF 2 7/8" CASING TO 1015' THAT MAY OR MAY NOT HAVE HAD ITS CASING CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/08/2003 12:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

A PLUGGING PACKER WAS SET IN THE 2 7/8" CASING AT 765' TO HALT FLOW FROM THE WELL. THE 2 7/8" CASING WAS PERFORATED AT 715'. 1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 725'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. THE WELL WAS TOPPED OFF AND THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE.

RECEIVED

NOV 17 2003 KCC

KCC WICHITA

RECEIVED

District #3

NOV 12 2003

Shanuta, KS

Remarks: THE SPOT LOCATION OF THIS WELL IS LIG-01 ON THE GPS SURVEY.

Plugged through:

District: 03

Signed

Clayton Titel by SL
(TECHNICIAN)

INVOICED

DATE 11-18-03

INV. NO. 2004060781