

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20635-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 16-16S-10W
915 feet from N Section Line, 825 feet from W Section Line
Lease/Unit Name: BOYE B Well Number: 1
County: ELLSWORTH Total Vertical Depth: 3336 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Production Casing Size: 4.5 feet: 3334 150 SX
Surface Casing Size: 8.625 feet: 326 175 SX *#108 42*

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2003 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: VERNON PHFLUEGEOFT Company: D S & W WELL SERVICING, INC. Phone: (620) 793-2440

Proposed Plugging Method: PER KCC RULES AND REGULATIONS

RECEIVED KANSAS CORPORATION COMMISSION NOV 17 2003 CONSERVATION DIVISION WICHITA, KS	RECEIVED KCC DISTRICT #2 NOV 7 2003 WICHITA, KS
--	--

Plugging Proposal Received By: VIRGIL CLOTHIER
Date/Time Plugging Completed: 11/07/2003 2:00 PM

Witness Type: Plugging Operations Partially Witnessed
KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sand off open hole to 3260' and put 4 sacks of cement on top. Shoot off 4-1/2" @ 1830'. Pull to 1300' and pump 35 sacks of cement. Pull casing to 950' and pump 35 sacks of cement. Pull casing to 375' and circulate cement to surface.
60/40 poz mix with 4% gel.

Remarks: ALLIED TICKET #14480

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED
DATE 11-18-03
INV. NO. 2004060775